Kvaerner's yard at Stord

19 March 2018 Steinar Røgenes, EVP EPCI



Kvaerner at Stord

Core business

- Module and platform assembly
- Onshore plant installation
- > Installation and hook-up
- > Platform demolition and recycling

1600 employees

- > 750 office
- > 850 non office






Established in 1919 as a herring oil factory







A leading ship yard in the 1970s






Oil and gas focused from 1975




















Improved productivity with new crane





Increased crane coverage and new deep sea quay More flexible yard – tailor made for floating facilities







Quay numbers

266_m

quay west

17 000_{m2}

production area west

100_m

extension of gantry crane

122_m

distance between pier and new quay

-16_m

water depth

15t/m2

area loads







51 new apprentices in 2017










Aasta Hansteen field development






Aasta Hansteen SPAR FPSO

Topside

- > Dry weight: 24 500 tonnes
- Conventional gas processing plant

Substructure

- > Total length: 200 m
- > Spar deck freeboard: 21 m
- > Hard tank diameter: 50 m
- > Displacement: 146 000 tonnes
- > Condensate storage: 25 000 Sm³





Kvaerner's Aasta Hansteen contracts



TechnipFMC

> Scope:

- Mooring
- Upending
- Ballasting
- Installation of predefined equipment
- Make ready for mating



> Scope:

- Fabrication of modules
- Inshore hook-up
- Offshore hook-up
- Commissioning assistance
- Completion





Towed to and anchored at Digernessundet




Submergence test

- > Executed in Q3 2017
- Submergence test down to 6 metres draft
- > Test to verify that SPAR was ready for mating





Inshore hook-up scope





Current project status for Kvaerner

- > Platform at Digernessundet, where inshore phase is being completed
- > Progress according to plan
- > HSSE: Zero lost time incidents
- > Sail-away from Stord early April
- Offshore hook-up to start summer 2018










Historical Decommissioning projects









Kvaerner's Disposal site - Stord



Deconstruction area with controlled drainage and deep water access.

The acquisition of GMC Decom has provided access to machinery, more decom resources, and extended decom area and quay.



Capacities

- > Tonnage at site: 60 000 tonnes
- > Permit to receive relevant hazardous materials and safely dispose these through approved disposal routes
- > Concrete area pads: 40 000m³, total processing area 80 000m³ incl. new areas.
- > Deepwater quaysides with waterdepth 26m and 32.5m
- > Access to cranes with high lifting capacity and inhouse multi-wheelers





Miller

> Client - Saipem UK (BP)

> Topside: 28 700 tonnes

> Substructure: 12 000 tonnes

> First modules received in 2017, remaining 37 000 tonnes to be delivered this summer by Saipem

> Scope: dismantle and recycle modules



Varg A



- > Client Saipem UK (Repsol)
- > Topsides weight: 900 tonnes
- Scope: deconstruction and recycling of topsides and mono-tower



Mono-tower weight:3 200 tonnes including concrete



Nyhamna Subsea compression plant



Removal and disposal of test plant at Nyhamna. Accommodate inspections. Approximate weight 2 200 tonnes. Duration August 2017 to autumn 2018.



Valhall QP topside & bridge



- Call off on frame agreement with Allseas for Aker BP decom work
- Scope: recycling of the topside and bridge
- > Work to be completed by spring 2020



Topside & bridge weight: 3 527 tonnes



Kvaerner – Decommissioning work scope

Studies

- > Overall planning of decommissioning
- > Removal and disposal studies
- > Mapping of hazardous materials

Preparation

- > Shutdown & cleaning of process systems
- > Hook-down to prepare for removal
- Mapping and removal/ sealing of hazardous materials

Blue text: Kvaerner with relevant competence Green text: Kvaerner already established/starting up Plugging and abandonment of wells

Offshore removal and transport

- > Preparation and removal of jackets, topside and subsea structures
- > Marine operations not requiring HLV
- > Inshore deconstruction and load-in


Onshore deconstruction and disposal

- > Make safe
- > Remove hazardous materials and equipment for sale
- > Deconstruction & segregation of materials
- Disposal Reuse and recycling maximised using best practical environmental option principle











Execution Locations






Progress



First cut 31.03.16



Last steel section installed 12.09.2017



First section into the assembly hall 21.10.16



Load out and jacking November 2017



Deliveries from Poland



Accommodation modules installed January 2018



Equipment installed



Heli deck & heli-hangar March 2018



Remaining main work

- > First half of 2018:
 - Installation of accommodation modules
 - Start loop testing
 - Heli-deck & heli-hangar installed
- > Second half of 2018:
 - Final weighing of topside
 - Mechanical completion
 - Completion and testing
- > Q1 2019:
 - Ready for sail-away and delivery







Illustration of ULQ sail-away





Sverdrup riser platform hook-up

- Contract value: NOK 450 million
- Kvaerner works in an integrated team with Aker Solutions
- Scope: Planning, management and hook-up of the seven platform modules
- Offshore hook-up and completion work to start early May



Process (P1)

Drilling (DP)








Njord A Upgrade Project

Elly Bjerknes, EVP Process Solutions
19 March 2018



KV/ERNER





NJORD LISENCE PARTNERS



50%



20%



20%



7.5%



2.5%





Njord A – delivered in September 1997





The platform was towed offshore only 28 months after cutting of the first steel plates.









EPC contract signed 17 March 2017











Client Statoil

Project

Upgrading of the Njord A semi-submersible platform.

Awarded

Frame agreement awarded 1 April 2016, EPC awarded 17 March 2017

Contract value

Around NOK 5.5 billion



Aker Solutions and Kvaerner in Verdal key suppliers







Njord:

A unique project

- > First NORSOK project
- > First production platform on NCS to be upgraded
- > Greenfield and brownfield in parallel
- > Hectic dock phase
- > Partly "hot work"
- > Challenging HSSE



Three main phases

PHASE 1: Yard stay, inspection, pre-EPC



PHASE 2: Dock phase: Increased buoyancy



PHASE 3: Further decom and upgrade work





Three main phases

PHASE 1:
Yard stay, inspection, pre-EPC




PHASE 2: Dock phase: Increased buoyancy



PHASE 3: Further decom and upgrade work









Dry dock numbers

4400 work permits

45 km welds (Repair rate 0,5%)

200 tons of steel (6349 items)

50.000 l of painting



3.500 tons of sand

60.000 m2 of painting


1.100 tons of scaffolding

1 ton of welding wire a week



Three main phases

PHASE 1: Yard stay, inspection, pre-EPC



PHASE 2: Dock phase: Increased buoyancy




PHASE 3: Further decom and upgrade work






























The Johan Castberg field



Location: 240 km north of the Snøhvit-field in the Barents Sea

Partners: Statoil (Operator 50%) Eni (30%) and Petoro (20%)

Water depth: 360-390 metres

Production start: 2022



Johan Castberg contracts

NOK 3.8 billion contract

Module fabrication contract

- 10 modules + flare
- Total weight: 14 645 tonnes
- Almost 10 000 tonnes of fabrication at Kvaerner

> Integration contract

- Install prefabricated modules
- Hook-up of modules at a total topside of more than 18 000 tonnes




Figure 2: Main FPSO topside and LQ/Utility areas, side view





Figure 3: Main FPSO topside and LQ/Utility areas, plan view



Johan Castberg FPSO





Execution locations and scope


- > Kvaerner's scope
 - Fabrication of modules (Verdal and Stord)
 - Integration and hook-up (Stord)
 - Testing and completion (Stord)
- Main subcontractors:
 - Aker Solutions (Egersund and Sandnessjøen)
- > Peak manning: around 2 000 employees and subcontractor personnel



70% Norwegian content



Project phases



2018 to 2020

Module
fabrication

Fabrication start in Q4 18 Almost 10 000 tonnes of modules to be fabricated at Kvaerner 2019 to 2020 **Interim phase**

Assembly of "stick built" modules for Integration phase
Hull arrival from Singapore
Q3 2020

2020 to 2022 **Integration phase**

Installation of all modules and Hook-up and integration between modules and Hull Commissioning and testing



Johan Castberg with Storen crane and quay expansion



KVERNER

Copyright and disclaimer

Copyright

Copyright of all published material including photographs, drawings and images in this document remains vested in Kvaerner and third party contributors as appropriate. Accordingly, neither the whole nor any part of this document shall be reproduced in any form nor used in any manner without express prior permission and applicable acknowledgements. No trademark, copyright or other notice shall be altered or removed from any reproduction.

Disclaimer

This Presentation includes and is based, inter alia, on forward-looking information and statements that are subject to risks and uncertainties that could cause actual results to differ. These statements and this Presentation are based on current expectations, estimates and projections about global economic conditions, the economic conditions of the regions and industries that are major markets for Kværner ASA and Kværner ASA's (including subsidiaries and affiliates) lines of business. These expectations, estimates and projections are generally identifiable by statements containing words such as "expects", "believes", "estimates" or similar expressions. Important factors that could cause actual results to differ materially from those expectations include, among others, economic and market conditions in the geographic areas and industries that are or will be major markets for Kværner's businesses, oil prices, market acceptance of new products and services, changes in governmental regulations, interest rates, fluctuations in currency exchange rates and such other factors as may be discussed from time to time in the Presentation. Although Kværner ASA believes that its expectations and the Presentation are based upon reasonable assumptions, it can give no assurance that those expectations will be achieved or that the actual results will be as set out in the Presentation. Kværner ASA is making no representation or warranty, expressed or implied, as to the accuracy, reliability or completeness of the Presentation, and neither Kværner ASA nor any of its directors, officers or employees will have any liability to you or any other persons resulting from your use.

